



- FACES:** 3M DIAMOND GRADE TRANSLUCENT DG3 REFLECTIVE SHEETING; SERIES 4090T AND 3M 1177C EC FILM; 3/16" THICK TRANSLUCENT LEXAN POLYCARBONATE SHEET – WHITE
- BACKGROUND:** 3M DIAMOND GRADE TRANSLUCENT DG3 REFLECTIVE SHEETING; SERIES 4090T AND 3M 1177C EC FILM; 3/16" THICK TRANSLUCENT LEXAN POLYCARBONATE SHEET – GREEN WITH REVERSED OUT COPY AND WHITE BORDER
- LOGO:** 3M DIAMOND GRADE TRANSLUCENT DG3 REFLECTIVE SHEETING; SERIES 4090T AND 3M 1177C EC FILM; 3/16" THICK TRANSLUCENT LEXAN POLYCARBONATE SHEET – PMS 329C TURQUOISE AND PMS 876C COPPER
- FONT:** HWY GOTHIC SERIES D (2002); STREET NAME AT NORMAL SPACING; WORD SPACING AT 400%
- ILLUMINATION:** GE TETRA EDGE STRIP HIGH OUTPUT GEBIH50-1 500K LED MODULE; 16 PER SIGN (8 TOP & 8 BOTTOM); I-GEPS24-100-NA POWER SUPPLY 1.1 AMPS @ 120 VOLTS
- CABINET:** 12" DEEP EXTRUDED ALUMINUM WITH MITERED CORNERS; 1-1/2" HINGED FACE FRAMES; MILL FINISH INSTALLATION; FLAG MOUNT BRACKETS
- SIZES:** SIGN LENGTH REDUCED TO PROVIDE 6' SIGN LENGTH AND 4' SIGN LENGTH IN ADDITION TO THE 8' SIGN LENGTH SHOWN

Typical Illuminated Street Name Sign Design Details

ILLUMINATED STREET NAME SIGNS

BID SCHEDULE

Bidder's Name: _____

ILLUMINATED STREET NAME SIGNS				
<i>Item No.</i>	<i>Item Description</i>	<i>Estimated Annual Quantity</i>	<i>BID Unit Price</i>	<i>Total Extended BID Price</i>
1A	20" x 8' Double Sided Sign Fabricate and Deliver to Site	4 EA	\$	\$
1B	20" x 8' Double Sided Sign Installation	4 EA	\$	\$
2A	20" x 8' Single Sided Sign Fabricate and Deliver to Site	2 EA	\$	\$
2B	20" x 8' Single Sided Sign Installation	2 EA	\$	\$
3A	20" x 8' Sign Replacement Face Fabricate and Deliver to Site	2 EA	\$	\$
3B	20" x 8' Sign Replacement Face Installation	2 EA	\$	\$
4A	20" x 6' Double Sided Sign Fabricate and Deliver to Site	4 EA	\$	\$
4B	20" x 6' Double Sided Sign Installation	4 EA	\$	\$
5A	20" x 6' Single Sided Sign Fabricate and Deliver to Site	2 EA	\$	\$
5B	20" x 6' Single Sided Sign Installation	2 EA	\$	\$
6A	20" x 6' Sign Replacement Face Fabricate and Deliver to Site	2 EA	\$	\$
6B	20" x 6' Sign Replacement Face Installation	2 EA	\$	\$
7A	20" x 4' Double Sided Sign Fabricate and Deliver to Site	4 EA	\$	\$
7B	20" x 4' Double Sided Sign Installation	4 EA	\$	\$
8A	20" x 4' Single Sided Sign Fabricate and Deliver to Site	2 EA	\$	\$

<i>Item No.</i>	<i>Item Description</i>	<i>Estimated Annual Quantity</i>	<i>BID Unit Price</i>	<i>Total Extended BID Price</i>
8B	20" x 4' Single Sided Sign Installation	2 EA	\$	\$
9A	20" x 4' Sign Replacement Face Fabricate and Deliver to Site	2 EA	\$	\$
9B	20" x 4' Sign Replacement Face Installation	2 EA	\$	\$
10	Signal Pole Extension when Installing Sign	1 EA	\$	\$
11	Maintenance Service 8' Cabinet Includes Cleaning, Re-lamping, etc.	4 EA	\$	\$
12	Maintenance Service 6' Cabinet Includes Cleaning, Re-lamping, etc.	4 EA	\$	\$
13	Maintenance Service 4' Cabinet Includes Cleaning, Re-lamping, etc.	4 EA	\$	\$
14	LED Field Retrofit of 8' Sign	1 EA	\$	\$
15	LED Field Retrofit of 6' Sign	1 EA	\$	\$
16	LED Field Retrofit of 4' Sign	1 EA	\$	\$
17	Sign Removal (all sizes) – Includes Sign, Brackets, Conduit, Brass Plug, Wiring to Hand-hole, Deliver to City Yard	4 EA	\$	\$
18	Misc. On-Site Labor – Skilled Journeyman Electrician *	20 HRS	\$	\$
19	Misc. On-Site Labor – Unskilled Electrician Technician *	20 HRS	\$	\$
20	Misc. On-Site Bucket Truck *	8 HRS	\$	\$
TOTAL BID PRICE				\$

*Note: Misc. on-site labor and bucket truck use is for on-call, as-needed, and where-needed electrician needs ***not associated*** with Bid Items 1 through 7.